



# Asansol Girls' College

(NAAC Accredited with 'A' Grade)  
(GOVT. SPONSORED)

Affiliated with The Kazi Nazrul University  
Dr. Anjali Roy Sarani, Asansol - 713304

Ph 0341-2257107 (Day), 2254098 (Morn) 2257600 (Principal), Fax : 0341-2257107

Website : [www.agc.ac.in](http://www.agc.ac.in) • E-mail :

[mail.agcorgin@gmail.com](mailto:mail.agcorgin@gmail.com)

Ref. No.....094/18.....

Date...23.05.2018...

Re - Tender

## Asansol Girls' College- Asansol -4

Re: Microbiology Lab-necessary repair & renovation of the existing room in 2<sup>nd</sup> floor  
at North East Corner of the Main College Building.

Sealed quotation is invited from experienced contractors, having GST Registration No, trade licence, PAN & Aadhar No to take up the above job at Girls' College as per following schedule.

The contractor is advised to fill up the format and submit at the college office Tender box within ten days from the date of this letter by 3 p.m.

Format properly filled in with necessary papers should be put in sealed envelope with name, address & phone no of the contractor, name & N.I.Q No of the job, written on top.

General Terms & Condition (See College web site) of the college Tender will apply U.O.S. Total time of completion is 2 (two) month.

Blank format might be downloaded from college Web site [www.agc.org.in](http://www.agc.org.in)

Estimated Amount Rs.116756.00

Sl. No.	Description of Job	Quantity	Unit	Rate in Rs	Amount Rs.	Remarks
1	Dismantling of the raised floor (Apx10 Mx1.5Mx400) to make it in line with extg floor.	6	Cu.M.			
2	Remove old, damp plaster on inside walls and ceiling, making new cement plaster, 20 <sup>th</sup> (1:6) for wall 10th (1:4) for ceiling including staging, curing etc.	105	Sq.M			
3	Colour painting (Acrylic Distemper to I/S wall & ceiling over a coat of Acrylic primer.	105	Sq.M			
4	Closing of one window with C.B.W.(1:6) and plaster (I/S & O/S) I/S plaster already included. Removing & cleaning of extg wooden frame & leaves.	0.6858	Cu.M			
5	Repairing and painting of old windows, 4nos (2No 1500X1200 & 2nos 1200X 600) with glass, fixtures etc 4.32 SQ.M for one side. For B/S=8.64 SQ.M.	8.64	Sq.M.			

Sl. No.	Description of Job	Quantity	Unit	Rate in Rs	Amount Rs.	Remarks
6.	Ordinary ceramic tile (300x300) X std thickness for flooring with 150 high skirting set in 20 <sup>th</sup> cement mortar (1:4) with 2th cement slurry on back of Tiles. Joints grouted with admixture of white cement and colour matching pigment.	40.0	Sq.M.			
7.	R.C.C. rack with granite top at window seal height on east side wall. 500 W x 8M lg x 65 <sup>th</sup> R.C.C. slab mounted with bracket or 3" th. wall	4.0	Sq.M.			
8.	4nos extg wooden table, Legs, & Sides to be cleaned and polished. Table top to be finished with sun micca top. 6' x 2'-6" table. Polishing Sun micca top.	18 9.6	Sq.M Sq.M			
9.	6Nos new wall mounted fan 300 Dia. S&F.	6	Nos.			
10.	Tuble light set-7nos. 2 nos 36 W tuble light with startar chock etc. In one PVC Box for each set with necessary wiring.	7	Set			
		Total Amount. Rs.				

Total Amount in words Rupees.....

Signature of Contractor.....

The Contractor is requested to submit as noted with his accepted Amount

C.C. Notice to be sent to P.W.D Notice Board.

Notice to be sent to A.M.C. Notice Board.

Notice to be sent for Publishing in local paper.

Notice to be given in college web Site.

*yhat* 28/5/18  
Teacher-in-Charge  
Asansol Girls' College  
Teacher-in-Charge  
Asansol Girls' College